

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Dickinson

(County)

Located In:

Corner Code #:

- 1. Public Land Survey T 42N R 27W 01  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Stephan J. Szyszkoski, in a field survey on July 01, 1993, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D1) Quarter corner common to Section 5 T42N-R27W and Section 32 T43N-R27W. Corner previously recorded in 1991 by Keith L. Sackett, RLS as a 1" IDx36" iron pipe with 4" aluminum cap placed midway and on line. 1991 NBTs as follows: 5" Sugar S50E 67.5', 5" Sugar S50W 67.2'. Found no subsequent record.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	1	2	3	4	5	6	7	8	9	10	11	12	13
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	29	30	31	32	33	34	35	36					
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D1) Recovered the remains of the 1991 monument at record bearing and distance from the stumps of the two 1991 NBTs. The top 12" of the pipe had been broken off, apparently by logging activity. The remainder of the pipe was still vertical and firmly set in the ground. The 1991 NBTs had been cut close to the ground, below any markings. I removed the remainder of the pipe and, in it's place, set a 1" ID x36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet. Marked 3 new bearing trees as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D1) Set 1"x36" pipe with 4" MDNR cap.  
Blazed and scribed the following new bearing trees (bearings magnetic):  
8" Sugar S39W 89.2' "1/4S NBT"  
5" Balsam S06W 93.4' "1/4S NBT"  
12" Sugar twin S22W 93.6' "1/4S NBT"  
Corner falls in a clearcut.



Signed by Stephan J. Szyszkoski Date 7-6-93  
Surveyor's Michigan License No. 33986