

MEMOR M-12 42-29

RECORDED

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

1999 JAN 28 AM 8:52

For corners in

Dickinson  
(County)

Located in:

Corner Code #

Felch Twp.  
1. Public Land Survey

T 42NR 28W A-12

T          

T          

T          

2. Property Controlling  
in Section

S      T      R     

3. Miscellaneous  
Property in Sec.

S      T      R     

S      T      R     

REGISTER OF DEEDS  
DICKINSON COUNTY  
RON MOORE

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_ SECTION \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert F. Perkins, in a field survey on June 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-12 West 1/4 Corner Section 31  
Post by William A. Burt, D.S. 1846  
Original Bearing Trees  
Sugar 20" N21°E 20 Lk.  
Sugar 16" S62 1/2°W 51 Lk.


ACCEPTED BY THE DICKINSON COUNTY  
SURVEY PEER GROUP AS THE OFFICIAL  
CORNER UNDER MICHIGAN PUBLIC ACT  
345 OF 1990 AT A MEETING HELD ON  
12-7-98  
RFP  
COUNTY REPRESENTATIVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-12 No Evidence of Original Corner  
or its Accessories Found.  
Found 5/8" x 24" Iron Pin buried in Road Centerline at Ancient Fence Line  
West and 2635.32' South of Section Corner to North. Location agrees with  
old Dickinson County Road Commission Data.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-12 Accepted Pin described in "B" above as Best Remaining Evidence of Corner  
Location and Replaced same with 2 1/2" Stamped D.C. Remon. Corner.  
Also Set 3 1/2" D.C. Remon. Witness Corner 20.00' West.  
New Witnesses:  
P.Pole #86-23599 N9°W(M.B.) 52.95' Nail/Tag  
P.Pole #86-23600 N85°E(M.B.) 186.02' Nail/Tag  
Spruce 6" S47°W(M.B.) 30.82' Nail/Tag  
Placed Carsonite Marker at Witness Corner.



Signed by Robert F. Perkins  
Surveyor's Michigan License No. 12027

Date Nov. 6, 1998