

Common Tran R 28W
G-1 ✓

RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1998 JUN 12 PM 12:40

For corners in

Dickinson (County)
Felch Township
1. Public Land Survey
2. Property Controlling in Section
3. Miscellaneous Property in Sec.
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Located In: T 43N R 28W
T _____ R _____
T _____ R _____
T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

Corner Code # G-13

REGISTER OF DEEDS
DICKINSON COUNTY
RON MOUNTAIN ST 49001

SURVEY &
REMONUMENTATION

NOV 15 1999

Register of Deeds Stamp & File Number

SECTION

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Edward Kazianka, in a field survey on May 19, 1998, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-13 Corner common to Sections 33, 34, 3 and 4.
Post by J. Burt, D.S. in June 1846.
Hemlock 12 N34E 41 lks. Sugar 14 N 02W 36 lks.
Sugar 10 S49E 20 lks. Sugar 14 S67W 17 lks.

1 1/4" inch iron pipe recorded by D. Babbit on 11-28-89.
Ironwood 4 S77W 30.9' (NBT). Maple 7 N76W 29.9' (S33 NBT).
" 8 N28E 26.8' (S34 NBT). Maple 10 S15E 32.9' (NBT).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13 1 1/4" iron pipe. Four NBT'S alive and standing.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 6-9-98
R. J. [Signature]
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 Set stamped D.C. Remon. corner in place of 1 1/4" iron pipe.
Ironwood 6 S77W 31.00 feet. Maple 8 N76W 30.04 feet.
" 8 N29E 27.15 feet. " 12 S15E 33.17 feet.
Carsonite Marker N45W 3.1 feet.

(Bearings are magnetic.)

igned by Edward Kazianka
urveyor's Michigan License No. 14765

Date June 5, 1998

