

SURVEY & REMONUMENTATION

DEC 18 1995

COMMISSION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

NOV 21 11:27

For corners in Dickinson Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 42N R 28W G-13
 T _____ R _____ H-13
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, Robert E. Perkins, in a field survey on Mar. 22, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-13 Southwest Corner, Section 34 Wm. A. Burt, D.S. 1847 Original Bearing Trees Sugar 12" N 8°E 29 Lks. Sugar 12" N52°W 24 Lks.

H-13 Southeast Corner, Section 34 Wm. A. Burt, D.S. 1847 Original Bearing Trees Tamarack 6" N60°E 25 Lks. Tamarack 5" N51°W 12 Lks.

ACCEPTED BY THE DICKINSON COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-20-95

RJP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: COUNTY REPRESENTATIVE

G-13 No evidence of Original Corner or Accessories Found. Corner Re-Established by Single Proportionate Measure between Section Corners. 2636.04' East and 2636.04' West.

H-13 No evidence of Original Corner or Accessories Found. Found 1½" Iron Pipe 20" high with Stamped Cap set by J.A. Sellik, C.E., State Highway Dept. 1937.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 Set 2½" Stamped Dickinson County Remonumentation Monument. Falls in old Woods Road in N-S Paint Line. New Witnesses Maple 4" S75°W (M.B.) 15.90' Maple 5" N68°E (M.B.) 23.50' Maple 5" S50°E (M.B.) 59.18' Maple 8" N05°W (M.B.) 14.37' Set Carsonite Marker ±1' East.

H-13 Accepted above found Iron Pipe Monument. New Witnesses B. Spruce 6" N44°W (M.B.) 20.15' B. Spruce 10" S34°W (M.B.) 27.61' B. Spruce 6" S85°W (M.B.) 47.75' Db1. Tam. 8" N68°E (M.B.) 43.83' Set Carsonite Marker ±1' S.W. of Corner.

Signed by Robert E. Perkins
 Surveyor's Michigan License No. 12027

Date Nov. 7, 1995

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS - JAN. 24, 1971

