

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
1 Dickinson
 (County)

Located in:

Corner Code #/1

1. Public Land Survey	T <u>42N</u> R <u>28W</u>	<u>L1</u>
	T _____ R _____	<u>N1</u>
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S <u>1</u> T _____ R _____	<u>1</u>
	S _____ T _____ R _____	<u>2</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

Register of Deeds Stamp & File Number

4. Lot No _____, Recorded Plat _____
 5. Private Claims _____

I, Keith Sackett, in a field survey on June 11, 1991, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

<u>L1</u>	<u>N1</u>	<u>1</u>	<u>2</u>
Original monument and accessories not found.	Found old post and 40" white pine stump original bearing tree.	Not set on original survey nor subsequently, apparently.	Not set on original monument nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<u>L1</u>	<u>N1</u>	<u>1</u>	<u>2</u>
Restored midway and on line.	Restored at post.	Established midway and on line.	Established midway and on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<u>L1</u>	<u>N1</u>	<u>1</u>	<u>2</u>
Set 1" ID x 32" iron pipe w/4" aluminum cap.	Set 1" ID x 32" iron pipe w/4" aluminum cap.	Set 1" ID x 32" iron pipe with 4" aluminum cap.	Set 1" ID x 32" iron pipe w/4" aluminum cap.
9" spruce S48E 9.0' 1/4s, NBT	4" balsam N55E 12.3' S31 NBT	6" cedar S40E 32.5' 1/16s BT	5" yellow birch N47W 6.0' 1/16s BT
7" white birch N79E 6.5' 1/4s, NBT	3" sugar N01E 27.0' S31 NBT	6" spruce East 31.2' 1/16s BT	6" yellow birch N34E 3.5' 1/16s BT
9" white birch N39W 12.1' 1/4s, NBT	8" sugar S69E 23.1' S6 NBT	6" white birch N62E 27.9' 1/16s BT	6" yellow birch S30W 14.0' 1/16s BT
4" sugar S45W 19.9' 1/4s, NBT			

Signed by Keith Sackett Date _____

Surveyor's Michigan License No. 19006

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983

