

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42N N.R. 28W


Dickinson COUNTY

DESCRIPTION OF CORNER Sec. cor. for Secs. 21-22-27-28

CORNER MONUMENT 1" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 11/4/66

WITNESSES TO CORNER..... X chisled on ledge, north, 09 lks.



10" W. Birch (S22)(NBT) N17°E, 82½ lks.

11" W. Birch (S27)(NBT) S13°E, 56 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by double proportioned measurement to sec. cors 1 mile to north and west ¼ cor. ½ mile to east. and face of ledge to south.

SURVEYOR'S SEAL

SIGNED *F. J. Bray*
F. J. Bray
REGISTERED LAND SURVEYOR

DATE 1/16/67