

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42N N. R. 27&28W


Dickinson COUNTY

DESCRIPTION OF CORNER Section corner for sections T42N, R28W 24 | 19 T 42N, R27W
25 | 30

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 9/26/62

WITNESSES TO CORNER..... 12" Elm (S24) (NBT) N76°E, 02½ links



CIRCLE CORNER REGISTERED

8" H. Maple (S25) (NBT) S15°W, 13 links

7" H. Maple (S19) (NBT) N19°E, 22½ links

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed on line and the single proportioned distance between section corner 1 mile north and 1/4 corner 1½ miles south.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE January 17, 1963
REGISTERED LAND SURVEYOR
Billy D. Buckler