


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Dickinson COUNTY  
T 42N R 26W

DESCRIPTION OF CORNER Section Corner 4, 5, 8, and 9  
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap  
DATE MONUMENT PLACED AND WITNESSED June 30, 1969

WITNESSES TO CORNER..... Sugar Maple 12 S44°W 15.6 feet "88 NBT"



Sugar Maple 6 N63°E 19.7 feet "84 NBT"

Sugar Maple 8 S16°E 17.2 feet "89 NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Monument placed at site of old squared 4"x4" pine post and a newer hard maple post. These monuments were found at the intersection of old fence lines from west and south, in the northeast corner of an old field clearing. Found no identifiable evidence of original monument or its accessories. This corner lies 39.90 chains southerly of an iron pipe purporting to be the East 1/4 corner of Section 5 (record: 40.00 chains). Found top of low hill, course southeast, descending gradually to south, at 3.00 chains south of corner, which agrees with the original field notes.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger  
REGISTERED LAND SURVEYOR

DATE

2/19/70

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68