

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY
T 42N R 28W

DESCRIPTION OF CORNER South 1/16 corner on N & S 1/4 line, Section 5

CORNER MONUMENT 1" I. D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 25, 1970

WITNESSES TO CORNER..... Y. Birch 11 S23°E (mag.) 26.6 ft. "1/16S, BT"



Red Maple 8 N 8°W (mag.) 35.0 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Not established in original survey.

Found a 3" x 3" x 4' squared post N15°E 38.9 ft. from corner established herein. Not accepted, because not correctly established.

Corner established on line between Center 1/4 corner 1321.7 ft. north and S1/4 corner 1321.8 ft. south.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE December 20, 1971

Arthur O. Enger

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68