

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42N N.R. 28W


Dickinson COUNTY

DESCRIPTION OF CORNER Section corner for sections 23-24-25-26

CORNER MONUMENT 1" pipe with 4" brass cap.

DATE MONUMENT PLACED AND WITNESSED 9-25-61

WITNESSES TO CORNER..... 8" Balm of Gilead (S26 NBT) S^oW 05 links



7" Balm of Gilead (S23 NBT) N^oW 11 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed at old Cedar (down) which has been blazed many years ago. Distance checks to stream 58 links north; good corner 1 mile west and good corner 1 mile south. Found old stake of unknown origin near Corner. Corner lies on a very old beaver dam.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE March 13, 1962
REGISTERED LAND SURVEYOR
Billy D. Buckler