

✓

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T~~42-43~~ NR ~~28-29~~ W

----- Dickinson ----- COUNTY

DESCRIPTION OF CORNER Township corner also section corner common to Sec.'s 6-1-36-31

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER 12" Tamarack stub S 71° W 46 links
"NBT"
9" Cedar stub N 25° W 71 links
"S 36 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Re-established section corner by double proportionate measure from corners:

Section corner 2 miles west.
 $\frac{1}{4}$ corner $\frac{1}{2}$ mile north.
Line tree ~~47.84~~ chs. south and possible line tree
6.04 chs. east.

Found old line of blazes west from corner; also found old cedar faced toward corner. Found possible cedar B.T. in proper position (no identifying marks).

Found very old cedar stake lying on ground near corner.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 9/5/57
REGISTERED LAND SURVEYOR