

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T⁴²⁼⁴³ NR 28W

Dickinson COUNTY

DESCRIPTION OF CORNER 1/4 cor. between secs: 3-34

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 16" W. Pine (1/4s NBT) S10^oW 28 1/2 Lks.

15" W. Pine (1/4s NBT) N20^oW 30 Lks.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced cor. at 30" W. Pine cor. tree. Found remains of old blazes and scar tissue. Found (probable) remains of W. Pine bearing N47^oW 57 Lks. from cor. Found numerous old blazes in vicinity. Squared and scribed 10" R. Pine at cor. Cor. placed and wit. 5/1/59 with H. S. Peterson, D.F.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 8/14/59
REGISTERED LAND SURVEYOR