

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T42N R28W and R29W  
T. 43N N.R. 28W and R29W


Dickinson COUNTY

DESCRIPTION OF CORNER Witness corner to Twp. corner common to T42N R28W and R29W and T43N R28W and 29W. This twp. corner is marked with a Department marker.

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED May 8, 1967

WITNESSES TO CORNER..... White pine 20" S 30 W 58 links, marked WC S1 BT



White pine 16" N 19 W 64 links, marked WC S36 BT

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This twp. corner is in an area which will be flooded by the East Branch of the Sturgeon River Watershed Project. A witness corner was established on the north line of section 6, T42N R28W a distance of 4.00 chains bearing S 89° 51' E from the corner.

Witness corner marked with a cedar post and iron pipe with aluminum cap marked WC in addition to corner identification.

Corner was placed 5-8-67 with John J. Fiorucci, Forestry Aid.

SURVEYOR'S SEAL

*H. S. Peterson*  
SIGNED H. S. Peterson DATE 5-11-67  
REGISTERED LAND SURVEYOR