

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Dickinson COUNTY


T 42-43N R 28W

DESCRIPTION OF CORNER West 1/16 corner between Sections 6 and 31

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED July 15, 1970

WITNESSES TO CORNER..... W. Pine 20 S69°E (mag.) 20.7 ft. "1/16S, BT"



W. Pine 16 N37°W (mag.) 48.0 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

**Not** established in original survey.  
No evidence that the corner had been established previously.

Corner established proportionately on line between 1/4 corner 1324.5  
ft. east and section corner 1296.6 ft. west.

Variation about 0°40' west.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger  
REGISTERED LAND SURVEYOR

DATE

December 20, 1971

Arthur O. Enger

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68