

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY
T 42-43N R 28W

DESCRIPTION OF CORNER 1/4 corner between Sections 6 and 31

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED July 14, 1970

WITNESSES TO CORNER..... Hemlock 14 S38°W (mag.) 14.5 ft. "1/4S, NBT"



Hemlock 10 West (mag.) 8.6 ft. "1/4S, NBT"

Sugar Maple 6 N6°E (mag.) 3.6 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

No subsequent monuments found, except for a 15" hemlock with old blazes on 4 sides 19.2 ft. west.

Corner re-established proportionately on line between section corner 2648.9 ft. east and section corner 2621.1 ft. west.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

December 20, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68