

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY
T 42 N R 28 W

DESCRIPTION OF CORNER North 1/16 corner between Sections 7 and 8

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED July 13, 1970

WITNESSES TO CORNER..... Cedar 12 S63°W (mag.) 23.8 ft. "1/16S, BT"



Cedar 7 N40°W (mag.) 24.3 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Not established in original survey.
No evidence that the corner had been established previously.

Corner established on line between section corner 1311.4 ft. north and 1/4 corner 1311.4 ft. south.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE December 21, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68