

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Dickinson COUNTY


T 42N R 28W

DESCRIPTION OF CORNER East 1/16 corner on E & W 1/4 line, Section 5

CORNER MONUMENT 3/4" solid round iron bar.

DATE MONUMENT PLACED AND WITNESSED March 26, 1970

WITNESSES TO CORNER..... Metal telephone junction box N1^oE (mag.) 18.7 ft.



Elm 4 N69^oW (mag.) 50.2 ft. "BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Not established in original survey.

Found a 3/4 " solid round iron bar in center of county road bed, purporting to be the subject corner and used for local metes and bounds surveys. Corner is 1.7 ft. westerly of true midpoint between controlling corners, which are 1326.1 feet west and 1329.5 feet east. Proceeding westerly on the quarter line, there is a 0^o26' right deflection at this corner.

As monument was near its calculated true position, it was accepted as found.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

December 20, 1971

Arthur O. Enger

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68