


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Dickinson COUNTY
T 42N R 28W

DESCRIPTION OF CORNER 1/4 corner between Sections 6 and 7
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED January 13, 1970
WITNESSES TO CORNER..... 8" x 4" dead cedar stub S52°E (mag.) 33 lks. "1/4S, NBT"



CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found an old 2" x 2" x 4' squared cedar post, apparently long used as the coded corner, although no original evidence could be identified. Post is neither on line between, nor at proportional distance to, section corners to E & W. (38.82 ch. to W and 40.24 ch. to E, versus 39.40 ch. and 40.00 ch. record distance and 39.23 ch. and 39.83 ch. proportional distance; and when proceeding westerly on section line there is a 1°18'20" left deflection at the 1/4 corner.) However, it checks reasonably well with stream and swamp crossings to E and swamp edge to W.

Perpetuated corner as found.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

Arthur O. Enger

DATE

December 27, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68