

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY  
T 42N R 28W

DESCRIPTION OF CORNER Section Corner 5, 6, 7, and 8

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED January 13, 1970

WITNESSES TO CORNER..... Cedar 7 S20°E (mag.) 44½ lks. "S8, NBT"



Cedar 6 S25°W (mag.) 45 lks. "S7, NBT"

Cedar 20 N88°W (mag.) 83 lks. "S6, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 2"x2"x14" squared cedar stake which has apparently been long used as the corner. Doubtful that it marks the original corner location, is perhaps 50 links too far south. This post is 79.48 ch. N of Sec. Cor. 7, 8, 17, 18 and 81.01 ch. S of Sec. Corner 5, 6, 31, 32, totalling 160.49 ch. for the two miles. The record distance between this corner and Sec. Cor. 7, 8, 17, 18 is 80.00 ch. and between this corner and Sec. Cor. 5, 6, 31, and 32 is 80.55 ch. totalling 160.55 ch; or a .06 ch. difference between measured and record distances. However, it was felt that moving the corner would create too much disturbance of local surveys, so it was perpetuated as is.

Corner accepted as found.

SURVEYOR'S SEAL

SIGNED

*Arthur O. Enger*  
REGISTERED LAND SURVEYOR

DATE December 27, 1971

DISTRIBUTION:

Arthur O. Enger

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68