


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Dickinson COUNTY
T 42N R 28W

DESCRIPTION OF CORNER 1/4 corner between Sections 5 and 6
CORNER MONUMENT 4" x 4" x 6 1/2" squared cedar post, scribed "1/4, 5, 6"
DATE MONUMENT PLACED AND WITNESSED March 31, 1970
WITNESSES TO CORNER..... Cedar 5 N 1/4 W (mag.) 67.4 ft. "1/4S, NBT"



Cedar 4 N 38 1/2° W (mag.) 70.4 ft. "1/4S, NBT"
Cedar 5 N 43 1/2° W (mag.) 95.3 ft. "1/4S, NBT"
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 2 1/2" x 2 1/2" x 4 1/2" squared cedar post, perhaps 20 years old, bearing S59°W 13.8 ft. from corner. This post measures 40.00 ch. north of a post at the SE corner of Sec. 5, leading to the conclusion that it was placed there in exactly that manner. No evidence to show that it was placed at the original corner.

Corner re-established proportionately on line between section corner 2647.5 ft. south and section corner 2699.2 ft. north.

Corner location is to be flooded by new impoundment. NBT's on ridge to N and NW of corner which will be an island.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE January 17, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68