

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY
T 42N R 28W

DESCRIPTION OF CORNER West 1/16 corner on E & W 1/4 line of Section 5

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED March 30, 1970

WITNESSES TO CORNER..... Cedar 10 S 42°E (mag.) 29.6 ft. "1/16S, BT"



Cedar 8 N18½°W (mag.) 2.1 ft. "1/16S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Not established in original survey.

Found an 11" balsam with blazes on 4 sides N42°E 17.2 ft. from corner and a 2-3 year old 3" x 3" x 4' squared cedar post N79°E 14.3 ft. from corner, set by unknown parties.

Corner established on line between W¼ corner 1324.7 ft. west and Center 1/4 corner 1324.7 ft. east.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

January 17, 1972

Arthur O. Enger

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68