

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY
T 42 N R 28 W

DESCRIPTION OF CORNER Center of Section 5

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED March 30, 1970

WITNESSES TO CORNER..... Hemlock 15 N31°E (mag.) 24.6 ft. "1/4S, BT"



Hemlock 10 S84°W (mag.) 13.3 ft. "1/4S, BT"

Hemlock 15 S64°E (mag.) 13.2 ft. "1/4S, BT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Not established in original survey.

Found a recent 2"x2"x4' squared yellow birch stake S26°E 10.3' from corner established herein, for an approximate corner.

Corner established on E & W quarter line at calculated intersection with calculated N & S 1/4 line, the assumption being that the N $\frac{1}{4}$ corner of Sec. 5 is at the midpoint of the north section line. (Corner not found). An E & W fence line begins at a point S88° 08' E 188.13 ft. from corner, then runs on a bearing of S89° 47.5' E. to the county road. Yellow birch stake is not on the westerly extension of this fence, and fence extended easterly would not hit the E $\frac{1}{4}$ corner of Sec. 5.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE January 18, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68