

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY  
T 42N R 28W

DESCRIPTION OF CORNER 1/4 corner between Sections 4 and 5

CORNER MONUMENT 3/4" O.D. iron pipe

DATE MONUMENT PLACED AND WITNESSED March 26, 1970

WITNESSES TO CORNER..... Y. Birch 17 N55°W (mag.) 40.8 ft. No new marks.\*



Sugar Maple 13 S18°E (mag.) 16.5 ft. No new marks.\*

\*\*

Sugar Maple 14 N 2°W (mag.) 18.1 ft. No new marks.\*

AND \* Old grown-over blazes facing corner.  
\*\* Southern-most of forked trees.

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 3/4" O.D. iron pipe in bed of a county road, set by unknown party on unknown date, but apparently used as the beginning point of several local metes and bounds surveys. Monument is neither on line between, nor at proportionate distances from, section corners to N & S. Distance N. is 40.73 ch., distance S is 39.83 ch., totalling 80.56 ch., the record distance being 80.55 ch. Northbound on section line, there is a left deflection of 0°34' at the quarter corner.

Accepted monument as found, although doubtful that it is in original corner location.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE

January 18, 1972

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68