


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Dickinson COUNTY
T 42N R 28W

DESCRIPTION OF CORNER 1/4 corner between Section 7 and 8
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED June 25, 1970
WITNESSES TO CORNER..... W. Pine stump 22 N11°E (mag.) 22.3 ft. "1/4S, NBT"



Balsam 10 S84°E (mag.) 24.0 ft. "1/4S, NBT"
Balsam 8 S18°W (mag.) 7.2 ft. "1/4S, NBT"
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a squared post S37°W 57 lks. and a cedar picket S51°W 74 lks. from corner for approximate corners, but measurements do not support them as probably being the true corner.

Corner re-established on line between section corners 2622.8 ft. to north and to south. Position checks within 35 links of a stream crossing north and is in general agreement with ridges to the south.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

January 18, 1972

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68