

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Dickinson COUNTY
T 42N R 28W

DESCRIPTION OF CORNER Section Corner 7, 8, 17, and 18

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED June 19, 1970

WITNESSES TO CORNER..... Balsam 6 S66°W (mag.) 11.4 ft. "S18, NBT"



W. Birch 6 N12°E (mag.) 21.6 ft. "S 8, NBT"

Balsam 6 S47°E (mag.) 23.2 ft. "S17, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 3"x3"x5½' squared cedar post, rotted off at ground level and lying on ground, with a down, burned cedar at about the record bearing and distance from it as the original BT recorded as being N11W 9 links from the corner. Could not find point of the post, but position checks very well with corners to the north and with natural features recorded in the original field notes to the north, south, and east of corner.

Accepted wood post as probably at the original corner position.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

January 18, 1972

Arthur O. Enger

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68