

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42N N.R. 28W


Dickinson COUNTY

DESCRIPTION OF CORNER Sec. cor. for secs. 13-14-23-24

CORNER MONUMENT 1" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 9/30/66

WITNESSES TO CORNER..... 10" H. Maple (S14)(NBT) N81°W, 04 lks.



14" H. Maple (S13)(NBT) N86°E, 20 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by double proportioned measurement
bet. sec. cors. 1 mile to north, south, east, and west.

No original evidence found.

SURVEYOR'S SEAL

SIGNED F. J. Bray DATE 1/13/67
REGISTERED LAND SURVEYOR