

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42N N.R. 28W


Dickinson COUNTY

DESCRIPTION OF CORNER Sec. cor. for secs. 8-9-16-17

CORNER MONUMENT 1" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 10/19/66

WITNESSES TO CORNER..... 7" H. Maple (S8)(NBT) N75°W, 30 lks.



8" H. Maple (S9)(NBT) N82°E, 45½ lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was placed at fence corner which checks well with cors. in vicinity. Y. birch stump bottom (rotted) in proper bearing and distance.

SURVEYOR'S SEAL

SIGNED F. J. Bray DATE 1/16/67
REGISTERED LAND SURVEYOR