

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	(DICKINSON COUNTY) LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>42</u> ^N X , R. <u>28</u> ^X W .	#L-8
2. PROPERTY CONTROLLING IN SECTION <u>24</u>	, T. <u>42</u> ^N S , R. <u>28</u> ^X W .	#12
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ ^N S , R. _____ ^E W .	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 19, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A Description of original monument and accessories and/or subsequent restoration:

Corner L8 (Center of Section 24, T42N, R28W) and

Corner 12 (South 1/16 corner on N & S 1/4 line, Section 24, T42N, R28W):
Neither of these corners established in original survey nor subsequently, apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner L8: Established at intersection of quarter-section lines. W 1/4 cor. is S89°39.9' W (true bearing) 40.094 ch.; E 1/4 cor. is N89°39.9' E (true) 40.131 ch., N 1/4 cor. is N 0°06.9'E (true) 40.064 ch.; and S 1/4 cor. is S0°06.9' W (true) 40.043 ch.

Corner 12: Established on line between S 1/4 cor. 20.0215 ch. S and Center 1/4 cor. 20.0215 ch. N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner L8: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
Red Maple 12 N43°W (mag.) 9.3 ft. "1/4S, BT"
Red Maple 7 S83°E (mag.) 13.9 ft. "1/4S, BT"
Declination 1°00' West.

Corner 12: 1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.
Cedar 18 N46°W (mag.) 24.7 ft. "1/16S, BT"
Cedar 8 S78°W (mag.) 18.8 ft. "1/16S, BT"
Declination 1°10' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Carl R. Johnson CHIEF OF SURVEY PARTY DATE August 13, 1978

APPROVED AND SIGNED BY Arthur O. Enger MICHIGAN REGISTERED LAND SURVEYOR DATE August 13, 1978

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

