

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	(DICKINSON COUNTY) LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION _____	32, T. 42 N. _____ S., R. 28 X. _____ W. _____	7
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on May 21 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner 7 (North 1/16 corner between Sections 32 & 33, T42N, R28W):**

Not set in original survey. Probably established (or purports to be the subject corner) in 1882 at the time of the making of the Re-Plat of the Village of Metropolitan, or at some time prior to that date. Local residents claim to have seen road construction crews pull out and throw away a wood stake marking the originally established location of this corner, when the streets of Felch Village were first paved.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner 7:** Position of corner recovered by collateral evidence of some perpetuated lot corners in the vicinity of the Felch School building. A survey of the school property was made by W. C. Johnson of the Dickinson County Road Commission about 1935, a sketch of which can be found in one of Johnson's field books for Felch Township, on file in the said Commission office. Position as restored agrees with observed lines of occupation of the lots fronting on Co. Rd. 569 and on other village streets, with distances agreeing virtually exactly with data shown on, or inferred from, the Re-Plat of the Village of Metropolitan.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner 7:** 2" PK-type nail with square shank, driven into the old sealcoat of the roadbed of Thirteenth Street at its intersection with the South line of Co. Rd. 569. Re-surfacing of the street in late 1979 has covered the nail so that it is no longer visible.

- (1) SE'ly corner of gas station-restaurant N35°57.5'E (true) 98.00 ft.
- (2) NW'ly corner of old concrete-block garage on lots 11 & 12, Block 3, S83°20.9'E (true) 49.27 ft. (Measurement to the cement block wall, not building foundation).
- (3) SW'ly corner of old concrete-block garage on Lots 11 & 12, Block 3, S48°29.9'E (true) 68.50 ft. (Also to wall blocks, not foundation.)
- (4) 5/8" x 16" round iron pin at NW corner of Lot 12, Block 3, N89°44.5'E (true) 37.47 ft.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_


SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE Jan 28 1979

Arthur O. Enger  
Michigan Registered Land Surveyor  
Michigan Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 13581