

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

DICKINSON COUNTY

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
2. PROPERTY CONTROLLING IN SECTION <u>32</u>	, T. <u>42</u> N. _____ S., R. <u>28</u> E. _____ W. _____	<u>#6</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ S., R. _____ E. _____ W. _____	_____
4. LOT NO. _____	RECORDED PLAT _____	_____
5. PRIVATE CLAIMS _____	_____	_____

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 23, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Corner 6 (Center of NE 1/4, Section 32, T42N, R28W):**  
 Not established in original survey, but apparently established (or purported to have been) in 1882, at, or prior to, the time of making of the Re-Plat of the Village of Metropolitan. Found a 1" iron pin about 6" below road surface of Co. Rd. 569.

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**Corner 6:** 1" iron pin found from detail on a survey sketch of the Felch School property, made by W. C. Johnson of the Dickinson County Road Commission c. 1935, which sketch is to be found in one of Johnson's field books for Felch Township, on file in the aforesaid Commission's office. The pin was there prior to Johnson's survey and its position conforms to observed occupation lines in the Village of Felch (originally called the Village of Metropolitan). Corner lies 7.2 ft. S of the yellow centerline stripe of Co. Rd. 569.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**Corner 6:** 1" iron pin of unknown length.  
 (1) White Ash 14 N12-1/2° E (true) 52.50 ft. "NBT"  
 (2) NW concrete foundation corner of main foundation of a frame house S 43° E (true) 42.20 ft.  
 (3) 5/8" x 18" round iron pin at NW corner of Re-Plat of Village of Metropolitan N89° 56.0' E (true) 120.22 ft.  
 Declination is 10° West.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE January 1980  
CHIEF OF SURVEY ARTY  
 MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

