

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

(DICKINSON COUNTY)

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>42</u> N. <u>X</u> R. <u>28</u> W. <u>X</u>	<u>#E-12</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on May 21, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E-12 (1/4 corner between Sections 32 & 33, T42N, R28W):
 No original evidence or subsequent physical evidence found. It is locally said that an iron pipe once marked the original corner position, but that it had long ago been pulled out by children at play.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E-12: Restored by collateral evidence from the N and E lot lines of Lot 1, Block 25, Re-Plat of the Village of Metropolitan, dated 10-19-1882. These lot lines were restored from collateral evidence obtained from a c. 1935 survey in the vicinity of Blocks 6, 7, 8, & 9 of the aforementioned plat, made by W. C. Johnson of the Dickinson County Road Commission, a sketch of which survey can be found in Johnson's field books for Felch Township, on file in the said Commission office.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner E-12: 1" I.D. x 36" iron pipe with 3-3/4" aluminum cap.
 (1) Red Maple 9 N54°W (mag.) 29.9 ft. "1/4S, NBT"
 (2) Hemlock 6 N11°E (mag.) 30.5 ft. "1/4S, NBT"
 (3) 5/8" x 18" round iron pin N25°44'00" E (true) 84.41 ft., buried in road at intersection of west line of Thirteenth Street and South line of old E & L.S. RR R.O.W.
 (4) 1" I.D. x 36" iron pipe, consisting of three 12-inch lengths welded together end to end, N55°06'40" E (true) 142.00 ft., at intersection of East line of Thirteenth Street and South line of old E & L.S. RR R.O.W. (Top of pipe at ground level).
 Declination 3°35' West.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE January 25 1979

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

