

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 42 N. R. 28 W.	C-11 & E-11
2. PROPERTY CONTROLLING IN SECTION	T. _____ S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 2, 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 Corner C-11 (Section Corner 29, 30, 31, & 32, T42N, R28W): and
 Corner E-11 (Section Corner 28, 29, 32, & 33, T42N, R28W):
 No evidence of original posts or accessories found. At Corner C-11 found a length of 3/4" re-inforcing rod driven into ground at an old farm fence corner and at Corner E-11 found a 1-3/4" O.D. iron pipe with a galvanized pipe cap marked "28, 29, 32, 33, T42N, R28W."

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner: Corner C-11: The found mon. appears to have been in place for an undetermined number of years. It bears N89°47.3'W 5272.2 ft., measured by EDM (record distance is 5272.1 ft.) from a mon. purporting to be Sec. Cor. 28, 29, 32, & 33; S89°47.4 E 5300.4 ft. EDM (record distance is 5289.9 ft.) from a monument purporting to be Sec. Cor. 25, 30, 31, & 36, T42N, R28-29W; and N0°01.5'E 5317.05 ft., calculated from 3-sided traverse, (record distance is 5280.0 ft.) from a monument at Sec. Cor. 5, 6, 31, & 32, T41-42N, R28W. Corner E-11: Monument found in place. Local stories are to effect that this mon. has moved from places where it had formerly been seen, to this location. Its present position in relation to other nearby monuments is noted above; additionally, it bears N0°17.5'W 2627.2 ft. (record is 2640.0 ft.) from 1/4 cor. bet. Sec. 32 & 33, a point of record since at least 1882.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Corner C-11: 3/4" re-inforcing rod, length unknown.
 Cedar 6 N 55°E (mag.) 46.5 ft. "S29, NBT"
 Cedar 7 S 65°E (mag.) 54.9 ft. "S32, NBT"

Corner E-11: 1-3/4" O.D. iron pipe, length unknown, with galv. pipe cap.
 Red Pine 8 S 64°E (mag.) 68.05 ft.
 Power Pole N 2°W (mag.) 40.16 ft.
 Distances are to a nail with brass DNR Ref. Point tag.
 Declination is 3°45' East.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger CHIEF OF SURVEY PARTY DATE February
 MICHIGAN REGISTERED LAND SURVEYOR

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

