

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Dickinson</u> (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>42N</u> R <u>28W</u>	<u>K-1, I-1, J-1.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Babbitt, in a field survey on 7/11, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- K-1. NE section corner of Section 2. 1" pipe w/4" brass cap. Mich. Cons. Dept. 1952. 8" spruce, S43E, 16 lks.; 6" spruce, N72W, 37 lks.
- I-1. NW section corner of Section 2. w. birch post, John Burt, D.S., 1846. w.pine 22, N25E, 30 lks.; hemlock 22, N45W, 38 lks.; y.pine 24, S25E, 29 lks.; hemlock 14, S66W, 30 lks.
- J-1. N 1/4 corner of Section 2. Cedar post, John Burt, D.S., 1846. Cedar 5", N80E, 22 lks.; DO 5", N57W, 17 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-1. Found brass capped Cons. Dept. monument. Both 1952 witnesses are in place but the SE one is dead and is now a broken off stub. Re-witnessed monument as found.
- I-1. Set by single proportion to the GLO record between the NE section corner of Section 2 and the N 1/4 corner of Section 3. Remains of w and y.pine stumps in the area but mostly very fragmented. The area has also burned very hard at some time in the past. Could not identify OBT'S.
- J-1. Set MPOL between the NE and NW section corners of Section 2. Cedar remains down and very rotten in the area but could not identify OBT'S.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|-----------------------------------|--------------------------|---------------------------|
| K-1. Brass Cons. Dept. Monument. | I-1. DNR Monument. | J-1. DNR Monument. |
| 4" spruce, S85W, 22.3' | 14" w.pine, S16W, 104.8' | 9" b.spruce, N55W, 26.35' |
| 7" spruce, N24E, 23.3' | 5" r.pine, S83W, 97.1' | 7" b.spruce, N22W, 16.9' |
| 7" spruce, S55E, 24.3' | 4" w.pine, N60W, 95.2' | 8" b.spruce, N32E, 19.7' |
| 9" spruce, N69W, 24.3' (1952 NBT) | 9" j.pine, S46E, 35.4' | 6" b.spruce, S33E, 13.15' |

Signed by David B. Babbitt

Date 11-28-89

Surveyor's Michigan License No. 21558