

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Dickinson</u> (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>42N</u> R <u>28W</u>	<u>G-5, G-4.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Babbitt, in a field survey on 6/20, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-5. SE section corner of Section 9. DNR Monument, F.J. Bray, RLS, January 16, 1967.
 11" w.pine, S53W, 44½ lks.; 21" w.pine, N5W, 74 lks.
- G-4. East 1/4 corner of Section 9. Cedar post, John Burt, D.S., 1850.
 W.pine 14, S43W, 34 lks.; DO 30, N43E, 64 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-5. Found DNR monument with stump of 21" w.pine, N3E, 49.7' and stub of 11" w.pine with bottom blaze and scribe marks plain--S60W, 29.5'. Re-witnessed monument as found.
- G-4. Set MPOL between the NE and SE section corners of Section 9. Some white pine remains in the area but badly rotted and burned, mostly fragments. Could not identify OBT's but this position fits the random line call for "ledge 40 ft." at 39.75 chains from the south reasonably well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| G-5. DNR Monument.
17" w.pine, S85E, 49.7'
4" maple, S30E, 15.0'
15" w.pine, S47W, 47.6'
(Pointed top on N88W, 57.2'
about ½ cu. yd.
boulder which extends above
ground about 18".) | G-4. DNR Monument.
5" w.birch, N75E, 15.55'
5" balsam, S80W, 5.0'
6" w.birch, N9W, 6.5'
Top of rock outcrop, South, 50'
Top of rock outcrop, S45E, 55' |
|--|---|

Signed by David B. Babbitt Date 11-28-89
 Surveyor's Michigan License No. 21558