

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Dickinson</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>4</u> T <u>42N</u> R <u>28W</u>	<u>12,13,16,15.</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Babbitt, in a field survey on 6/29, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 12. South 1/16 corner of Section 4. No previous record.
- 13. SE 1/16 corner of Section 4. No previous record.
- 16. East 1/16 corner on the South section line of Section 4. No previous record.
- 15. West sixteenth corner on the South section line of Section 4. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 12. Set MPOL between the South 1/4 corner and the center of Section 4.
- 13. Set at the computed center of the SE 1/4 of Section 4 by closed traverse. There is a large rock under this monument about 6" below ground surface so I dug pits 6' NW and 6' SE from the monument and used the soil dug out to mound up around the monument to hold it upright.
- 16. Set MPOL between the South 1/4 corner and the SE section corner of Section 4.
- 15. Set MPOL between the South 1/4 corner and the SW section corner of Section 4.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|---|---|---|
| 12. DNR Monument.
5" maple, S47E, 30.75' | 13. DNR Monument.
5" balsam, N82W, 43.4' | 16. DNR Monument
4" cedar, S22W, 11.9' |
| 6" maple, S2W, 25.7' | 6" aspen, N67W, 43.1' | 5" cedar, N67W, 21.4' |
| 5" maple, S87W, 24.25' | 1" spruce, N60E, 11.1' | 5" cedar, N38E, 24.85' |
| 9" maple, N46E, 8.1' | Chiseled + on top of 1/2
cu. yd. | 4" cedar, S17E, 29.25' |
| | Gray rock, S84E, 13.05' | |

- 15. DNR Monument
7" maple, N15E, 17.55'
- 6" maple, S26E, 57.4'
- 5" maple, S18W, 22.0'
- 6" maple, N65W, 39.3'

Signed by David B. Babbitt Date 11-28-89
 Surveyor's Michigan License No. 21558