

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Dickinson</u> (County)	Located In:	Corner Code \neq
1. Public Land Survey	T <u>42N</u> R <u>28W</u>	<u>G-2, G-1, F-1.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, David B. Babbitt, in a field survey on 6/26, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- G-2. East 1/4 corner Section 4. Maple post, John Burt, D.S., 1850. Lynn 12, S50W, 4 lks. Sugar 14, N42E, 20 lks.
- G-1. NE section corner of Section 4. Hemlock post, John Burt, D.S., 1846. Hemlock, 12, N34E, 41 lks.; Sugar 14, N2W, 36 lks.; Sugar 10, S49E, 20 lks.; Sugar 14, S67W, 17 lks.
- F-1. North 1/4 corner of Section 4. Hemlock post, John Burt, D.S., 1846. Hemlock 18, N34E, 30 lks.; DO 17, N17W, 11 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-2. Set by single proportion to the GLO record between the SE and NE section corners of Section 4. Corner falls in E-W dirt graded road.
- G-1. Found 1 1/2" pipe beside very old 4"x4" cedar post. Origin unknown but measurements to other known corners in the area are reasonable and local landowners in the area all seem to accept this pipe as the section corner. I have, therefore, accepted it. Witnessed pipe as found.
- F-1. Found 1 1/2" pipe of unknown origin. Measurements to other known corners in the area are reasonable and all local landowners seem to accept this pipe as the 1/4 corner. I, therefore, have accepted it. Witnessed pipe as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|-----------------------------------|--------------------------|-------------------------|
| G-2. DNR Monument buried in road. | G-1. 1 1/2" pipe. | F-1. 1 1/2" pipe. |
| 7" h.maple, S33E, 40.7' | 4" ironwood, S77W, 30.9' | 4" maple, S56W, 24.9' |
| 7" h.maple, S12W, 44.4' | 7" maple, N74W, 29.9' | 7" maple, N12W, 15.05' |
| 7" cherry, N35W, 40.2' | 8" ironwood, N28E, 26.8' | 17" w.pine, N55E, 42.2' |
| 8" aspen, N49E, 35.1' | 10" maple, S15E, 32.9' | 8" maple, S23E, 3.8' |

Signed by David B. Babbitt Date 11-28-89
 Surveyor's Michigan License No. 21558