

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Dickinson</u> <small>(County)</small>	Located In:	Corner Code \neq
1. Public Land Survey	T <u>42N</u> R <u>28W</u>	<u>G-3, F-2, F-3.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Babbitt, in a field survey on 7/3, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-3. SE section corner of Section 4. Cedar post - John Burt, D.S.-1850. Cedar 8 - S17E, 14 lks. DO 10 - N57W, 18 lks.
- F-2. Center quarter corner of Section 4. No previous record.
- F-3. South 1/4 corner of Section 4. Wood post - John Burt, D.S. - 1850. Hemlock 14, S70E, 21 lks
Y.birch 16, N81W, 26 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-3. Set by double proportion to the GLO record from section corners 1 mile north, 1 mile south, 1 mile east, and 1 mile west. Several down cedars in the area but could not identify OBTs. One down cedar a short distance almost directly west shows old line blazes on both E & W sides of it. It is very old and rotten and could even have been marked at the time of the original survey but not of record. Fits swamp call 1 chain north.
- F-2. Set at the intersection of the N-S and E-W 1/4 lines of Section 4.
- F-3. Set MPOL between the SE and SW section corners of Section 4. Could not identify OBTs--old down sq. cedar post leaning on nearby tree but could not tell where it stood.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | |
|----------------------------|--------------------------|------------------------|
| G-3. DNR Monument | F-2. DNR Monument | F-3. DNR Monument |
| 6" b. spruce, N14W, 11.7' | (Buried in Road) | 8" maple, N44E, 27.85' |
| 4" b. spruce, N80E, 12.3' | 5" maple, N44E, 36.9' | 7" maple, S37E, 30.5' |
| 12" b. spruce, S35E, 41.7' | 8" maple, S30E, 30.95' | 8" maple, S55W, 10.9' |
| 6" b. spruce, S24W, 20.5' | 6" maple, S37W, 37.1' | 8" maple, N41W, 21.7' |
| | 4" ironwood, N39W, 38.3' | |

Signed by David B. Babbitt Date 11-28-89
 Surveyor's Michigan License No. 21558