

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson
(County)

Located In:

Corner Code ##

- | | | | | | | | |
|---------------------------------------|---|----------|---|------------|-------|------------|---------------|
| 1. Public Land Survey | T | _____ | R | _____ | _____ | | |
| | T | _____ | R | _____ | _____ | | |
| | T | _____ | R | _____ | _____ | | |
| | T | _____ | R | _____ | _____ | | |
| 2. Property Controlling
in Section | S | <u>9</u> | T | <u>42N</u> | R | <u>28W</u> | <u>7, 14.</u> |
| | S | _____ | T | _____ | R | _____ | _____ |
| 3. Miscellaneous
Property in Sec. | S | _____ | T | _____ | R | _____ | _____ |
| | S | _____ | T | _____ | R | _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, David B. Babbitt, in a field survey on 6/20, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

7. N 1/16 corner on the E section line of Section 9. No previous record.
14. South 1/16 corner on the E section line of Section 9. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

7. Set MPOL between the East 1/4 corner and the NE section corner of Section 9.
14. Set MPOL between the East 1/4 corner and the SE section corner of Section 9.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|------------------------|---------------------------|
| 7. DNR Monument | 14. DNR Monument |
| 6" cedar, N40W, 25.5' | 12" w. pine, N13E, 28.25' |
| 4" cedar, N6E, 22.8' | 6" cedar, N20W, 21.35' |
| 6" cedar, South, 35.1' | 7" cedar, S25W, 22.45' |
| 5" cedar, N76W, 13.0' | 7" cedar, S38E, 21.0' |

Signed by David B. Babbitt

Date 11-28-89

Surveyor's Michigan License No. 21558