

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Dickinson  
(County)

Located In:

Corner Code *≠*

- |                                    |                           |                       |
|------------------------------------|---------------------------|-----------------------|
| 1. Public Land Survey              | T <u>42N</u> R <u>28W</u> | <u>H-2, H-3, I-2.</u> |
|                                    | T _____ R _____           | _____                 |
|                                    | T _____ R _____           | _____                 |
|                                    | T _____ R _____           | _____                 |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____                 |
|                                    | S _____ T _____ R _____   | _____                 |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____                 |
|                                    | S _____ T _____ R _____   | _____                 |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Babbitt, in a field survey on 6/28, 19 89, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- H-2. Center quarter corner of Section 3. No previous record.
- H-3. South 1/4 corner of Section 3. Cedar post, John Burt, D.S., 1850. Spruce 8", S34W, 30 lks. Spruce 8", N54E, 21 lks.
- I-2. East 1/4 corner of Section 3. Wood post, John Burt, D.S., 1850. Y.Birch 10, S30W, 23 lks. Sugar 14, N73E, 19 lks.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

- H-2. Set at the intersection of the N-S and E-W 1/4 lines of Section 3.
- H-3. Set MPOL between the SE and SW section corners of Section 3. No sign of OBTs but monument falls in front of very old cedar sign up tree and in line of very old blazes east and west.
- I-2. Found 1 1/2" pipe not of record. Could not locate OBT's. Found pipe is about 3' South of prop. to GLO and is about 18' East of a straight line from section corner to section corner. Drove pipe of DNR monument inside of 1 1/2" pipe and marked NBT's as indicated below.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |                           |                        |                                   |
|---------------------------|------------------------|-----------------------------------|
| H-2. DNR Monument.        | H-3. DNR Monument      | I-2. DNR Monument in 1 1/2" pipe. |
| 13" maple, S44W, 25.9'    | 6" cedar, N46E, 14.6'  | 7" maple, N32E, 55.5'             |
| 10" maple, S81W, 52.0'    | 6" cedar, S14E, 12.85' | 3" ironwood, S24E, 25.3'          |
| 12" maple, N63W, 47.3'    | 7" cedar, S61W, 23.8'  | 9" maple, S35W, 20.3'             |
| 9" twin maple, N4W, 83.1' | 8" cedar, S87W, 10.55' | 5" maple, N6W, 9.0'               |

Signed by David B. Babbitt Date 11-28-89

Surveyor's Michigan License No. 21558