

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Dickinson  
County

Located In:

Corner Code #

- 1. Public Land Survey T 42N R 28W ES
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Stephen J. Szyzloski, in a field survey on November 21, 1992, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

(ES) Section corner common to sections 8-9-16-17. Corner previously recorded by Frank J. Gray RLS in 1967 as monumented by a 1" iron pipe with 4" aluminum cap and the following NBTs: 7' N. Maple (S8) (NBT) N75W 30 links, 8' N. Maple (S9) (NBT) N82E 45.5 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(ES) Recovered monument as described at record bearing and distance from the N. Maple N75W NBT. The N. Maple in the NE quadrant has been cut. Rewitnessed the monument as found, marking two new NBTs, described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(ES) Fd. 1" pipe with 4" aluminum MNBR cap.

Blazed and scribed the following new bearing trees:

8" sugar N49E 38.0' "S9 NBT"

8" sugar S56E 47.2' "S16 NBT"

A fence cor. post is west of the corner, 0.5'.

Signed by

*Stephen J. Szyzloski*

Date

8-23-93

Surveyor's Michigan License No.

33986