

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located In:

Corner Code #:

- 1. Public Land Survey T 42N R 28W 87
- T R
- T R
- T R
- 2. Property Controlling S 18 T 42N R 28W 8
- In Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

87 February 06, 1995

I, Stephan J. Szyszkoski, in a field survey on 8 February 02, 1995, 19____ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- (87) Quarter corner common to Sections 18-19. Corner established in 1850 by John Burt as follows: Set cedar qr. section post. Tamarack 8 S41E 23, Spruce 10 N8W 19. Found no subsequent record.
- (8-Sec. 18) West 1/16 corner Section 18. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (87) Original post and accessories not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the corner at the position proportionate to the original record, on a straight line and at the midpoint between sections corners 2651.46' east and west. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.
- (8-Sec. 18) Found no evidence of prior monumentation at the corner position. Established the corner at 20 chains, proportionate to the original record (mean of north and south lines of Sec. 18) west of the Center of Section 1312.29' east, and on a straight line between Center and quarter corner 1296.55' west. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|--|
| (87) Set a 1" iron pipe with 4" MDNR cap. Blazed and scribed the following witnesses: | (8) Set a 1" iron pipe with 4" MDNR cap. Blazed and scribed the following witnesses: |
| 5" Cedar S59E 6.2' "1/4S NBT" | 5" Cherry S22W 13.9' "1/16S BT" |
| 5" Cedar N59E 14.0' "1/4S NBT" | 20" Tamarack S69E 78.1' "1/16S BT" |
| 5" Cedar N70W 15.5' "1/4S NBT" | 12" Spruce N34E 40.3' "1/16S BT" |
| 5" Cedar S53W 14.7' "1/4S NBT" | 11" Balsam N30W 45.7' "1/16S BT" |
| Bearings are magnetic. | Bearings are magnetic. |



Signed by Stephan J. Szyszkoski Date 2-22-95
Surveyor's Michigan License No. 33986