

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------------------|-----------|
| 1. Public Land Survey | T <u>42N</u> R <u>28W</u> | <u>A6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S <u>18</u> T <u>42N</u> R <u>28W</u> | <u>6</u> |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on 06 November 09, 1994, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

(A6) Quarter corner common to Section 18 T42N-R28W, and Section 13 T42N-R29W. Corner established in 1846 by John and Austin Burt as follows: "40.00 Set cedar post. Fir 5 S24W 16, Cedar 5 N25W 12." Original line notes show: south 1.5 ch. swap edge, south 4.21 ch. 60' cliff, north 2.0 ch. swap edge. Found no subsequent record.
 (6-Sec. 18) Northeast 1/16 corner, Section 18. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A6) Original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Found no evidence of subsequent monumentation. Corner falls in an alder marsh. Recovered several small cedar stumps and boles submerged in the water at the corner location, but none with any markings. Reestablished the corner by proportionate measurement to the original record, on a straight line between Section corners 7923.1 ft. north and south. The line calls noted above all check very well - the cliff, a 60' vertical drop, is at record distance south of the reestablished corner. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.
 (6-Sec. 18) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite 1/16 corners, all monumented. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | |
|---|--|
| (A6) Set a 1" iron pipe with 4" MDNR cap. Blazed and scribed the following witnesses: | (6) Set a 1" iron pipe with 4" MDNR cap. Blazed and scribed the following witnesses: |
| 20" Tamarack N77E 56.5' 1/4S NBT" | 8" Cedar N41W 5.8' 1/16S BT" |
| 16" B. Spruce N29E 63.5' 1/4S NBT" | 8" Cedar N47E 18.4' 1/16S BT" |
| 6" B. Spruce S35E 55.4' 1/4S NBT" | 8" Cedar S01W 71.8' 1/16S BT" |
| 8" spruce stump, freshly cut N13E 31.5' marked "NBT" | 10" Cedar S49W 43.2' 1/16S BT" |
| Set a squared spruce post adjacent. Bearings are magnetic. | Placed a location poster on a 12" W. Birch snag N58E 5.5'. Bearings are magnetic. |



Signed by Stephan J. Szyszkoski Date 2-22-95
 Surveyor's Michigan License No. 33986