

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Dickinson

(County)	Located In:	Corner Code #
1. Public Land Survey	T 42N R 28W	85
	T R	
	T R	
	T R	
2. Property Controlling in Section	S 18 T 42N R 28W	5
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Stephan J. Szyszkoski, on 5 January 30, 1995, in a field survey on 85 January 31, 1995, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5	●												
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(85) Quarter corner common to Sections 7-18. Corner established in 1850 by John Burt as follows: "Set Y. Birch qr. Sec. post. Y. Birch 16 S31W 31, Cedar 14 N33E 27". Line notes show stream 5 links C. S.W. crossing 13.0 chains east of the corner. Record distances east and west to adjacent section corners are 40.00 ch. and 39.52 ch. respectively. Found no subsequent record.  
(5-Sec. 18) North 1/16 corner, Section 18. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(85) Original post not recovered. Remonumented the corner at the original position as determined from the remains of the two original bearing trees, a 20" Y. Birch stump, rotted but showing traces of old lower blaze overgrowth facing the corner, and an 18" rotted Cedar stump, no markings visible. Both were found at record bearing and distance. The record bearings were determined to be astronomic bearings. Cut the Y. Birch and recovered traces of old blaze but no scribing. Found the stream, as described, at record distance east. Distances east and west to adjacent corners were found to be 40.482 ch. and 38.882 ch. respectively. At the position for the corner, I placed a 1" I.D.x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.  
(5-Sec. 18) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between Center of Section 8 1338.0' south and quarter corner 1338.0' north. At the position for the corner, I placed a 1" I.D.x32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(85) Set a 1" iron pipe with 4" MDNR cap. Blazed and scribed the following witnesses:	(5) Set a 1" iron pipe with 4" MDNR cap. Blazed and scribed the following witnesses:
20" Cedar N40E 29.5' 1/4S NBT	5" Spruce N02W 5.3' 1/16S BT
6" Cedar N48W 49.9' 1/4S NBT	7" Spruce N78E 6.7' 1/16S BT
10" Cedar S44W 51.6' 1/4S NBT	7" Cedar S14E 33.5' 1/16S BT
6" Ash N05W 12.6' 1/4S NBT	6" Cedar S56W 18.75' 1/16S BT

Placed a 5" squared cedar post adjacent. Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 2-22-95  
Surveyor's Michigan License No. 33986