

151

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson

(County)

Located In:

Corner Code ##

1. Public Land Survey	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
	T	_____	R	_____	_____		
2. Property Controlling in Section	S	<u>18</u>	T	<u>42N</u>	R	<u>28W</u>	<u>4</u>
	S	<u>18</u>	T	<u>42N</u>	R	<u>28W</u>	<u>7</u>
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____	_____
	S	_____	T	_____	R	_____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

7 January 31, 1995

I, Stephan J. Szyszkoski, in a field survey on 4 January 30, 1995, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

(4-Sec. 18) Northwest 1/16 corner, Section 18. Corner not established in the original survey. Found no subsequent record.
 (7-Sec. 18) North 1/16 corner between Sections 17 and 18. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(4-Sec. 18) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite 1/16 corners, all monumented. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.
 (7-Sec. 18) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between section corner and quarter corner 1342.8' north and south. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(4) Set a 1" iron pipe with 4" MDNR cap.

Blazed and scribed the following

witnesses:

18" Spruce S09W 37.3' "1/16S BT"
 16" Spruce N89E 27.4' "1/16S BT"
 14" Spruce N66W 31.8' "1/16S BT"
 3" Spruce N25E 20.4' "1/16S BT"

Squared and scribed an 11" poplar N41W.

Bearings are magnetic.

(7) Set a 1" iron pipe with 4" MDNR cap.

Blazed and scribed the following

witnesses:

5" Maple S82E 36.0' "1/16S BT"
 10" Spruce S26E 53.0' "1/16S BT"
 5" Cedar S59W 44.6' "1/16S BT"
 8" Balsam N02W 23.2' "1/16S BT"

Found an iron fence post N67E 3.6'

Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 2-22-95
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division.

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 29, 1971
 REVISED MAY 14, 1976
 REVISED JAN., 1983