

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
Dickinson

(County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 18 T 42N R 28W	2
	S 18 T 42N R 28W	1
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5	•	•											
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 2 February 01, 1995, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (2-Sec. 18) East 1/16 corner between sections 7-18. Corner not established in the original survey. Found no subsequent record.  
 (1-Sec. 18) West 1/16 corner between Sections 7-18. Corner not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (2-Sec. 18) Found no evidence of prior monumentation at the corner position. Established the corner midway and on a straight line between quarter corner and section corner 1335.92' west and east. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.  
 (1-Sec. 18) Found no evidence of prior monumentation at the corner position. Established the corner at 20 chains, proportionate to the original record, on a straight line between 1/4 corner 1298.68' east and Section corner 1267.52' west. At the position for the corner, I placed a 1" I.D. x 32" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |  |
|---|--|
| (2) Set a 1" iron pipe with 4" MDNR cap.<br>Blazed and scribed the following witnesses:<br>4" Sugar N20W 18.7' "1/16S BT"<br>8" Spruce S86E 46.7' "1/16S BT"<br>3" Maple S16E 19.0' "1/16S BT"<br>4" Sugar S80W 35.7' "1/16S BT"<br>Found a iron fence post S77W 18.4'.<br>Placed a 3/4" iron pipe, projecting 1.8', south 0.8', to make corner more apparent, as it falls in a depression.<br>Bearings are magnetic. | (1) Set a 1" iron pipe with 4" MDNR cap.<br>Blazed and scribed the following witnesses:<br>6" Spruce N64M 16.3' "1/16S BT"<br>7" Spruce S20W 26.7' "1/16S BT"<br>6" Spruce S39E 31.8' "1/16S BT"<br>4" Spruce N03N 9.9' "1/16S BT"<br>Bearings are magnetic. |
|---|--|



Signed by Stephan J. Szyszkoski Date 2-22-95  
 Surveyor's Michigan License No. 33986