

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson

(County)	Located in:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>28W</u>	<u>17</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>22</u> T <u>42N</u> R <u>28W</u>	<u>2</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on November 28, 1994, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(17) Corner common to Sections 14-15-22-23. Corner reestablished and filed in 1967 by F.J. Bray, RLS as follows: Reestablished by double proportionate measurement between sec. cors. 1 mile north, south and west and 2 miles to east. Placed 1" iron pipe with 4" aluminum cap. Witnesses: 12" Elm N71E 12.5 links, 10" Elm S75W 37 links. Found no subsequent record.
 (2-Sec. 22) East 1/16 corner between Sections 15-22. Corner established and filed in 1967 by F.J. Bray, RLS as follows: This corner placed midway and on line bet. 1/4 cor to west and sec. cor to east. Corner monument - 1" iron pipe with 4" aluminum cap. Witnesses: 12" Elm N46E 11 links, 12" Elm N64W 13.5 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(17) Found the monument as described above, in good condition, and at record bearing and distance from the remaining NBT: 10" elm S80W 24.4', now dead. The other elm is now a badly deteriorated stump. Left the monument in place and marked 4 new witnesses as described below.
 (2-Sec. 22) Found the monument noted above at record bearing and distance from the stump remains of the Elm bearing tree N64W. The other elm NBT is dead and down. The aluminum cap has been broken off of the monument, but it is otherwise in good condition. Left the pipe in place and marked 4 new witnesses as described below. Found a 3/8" iron rod set by unknown persons, with the remains of a plastic cap, apparently chewed on by some animal, N78E 3.1' distant.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(17) Found 1" iron pipe with 4" HDNR tablet. Blazed and scribed the following new bearing trees:
 14" Maple N69W 16.6' "S15 NBT"
 8" Maple N29E 6.5' "S14 NBT"
 9" Maple S40W 6.9' "S22 NBT"
 7" Maple S50E 23.0' "S23 NBT"
 Bearings are magnetic.

(2) Found 1" iron pipe with broken aluminum cap. Blazed and scribed the following new bearing trees:
 10" Maple S89E 3.5' "1/16S BT"
 10" Maple N05E 18.2' "1/16S BT"
 12" Maple S36E 12.6' "1/16S BT"
 7" Sugar N81E 28.5' "1/16S BT"
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 2-22-95
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division.