

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Dickinson
 (County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>42N</u> R <u>28W</u>	<u>C6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on February 01, 1995, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

(C6) Quarter corner common to Sections 17-18. Corner established in 1850 by John Burt as follows: "Set spruce quarter section post. Cedar 12 S26E 47, Cedar 10 N55N 20." Random line notes for the line between 17-18 by E.C. Martin, 1850, run from the north, are as follows: 1) 2.25 Descend greenstone ledge C. MNW, 2) 5.00 Foot of Do 100 and enter windfall C. ENE, 3) 9.50 Stream 25 links C.W, 4) 28.50 Descend Ledge of Mica slate 100 feet. Dip nearly vertical with the horizon, 5) 29.50 Foot of Do C.E&W and enter swamp C.E&W, 6) 40.00 Set temporary post, 7) 41.00 Leave swamp C. E&W, 8) 45.00 Enter swamp and Leave windfall C. SE, 9) 64.30 Intersect stream 100 C. SSE, 10) 76.50 passed stream by offset, 11) 80.00 Intersect line 100 west of post. Land except swamp rocky and hilly.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C6) Original post and accessories were not recovered. There are a number of old cedar stumps in the corner area, most showing signs of being burnt. None of the stumps would match the record. The distance between C5 and C7 as filed by Enger and Bray measures 80.790 ch (52' longer than record). Both corners appear to have been re-monumented in accord with the original record and are accepted here as being at the original positions. I believe that the nearly 1 ch. error in the measure of this line was made in the n'y 1/2 mile of the original survey. I base this on measurements to well defined feature calls made on the random line and the fact that the n'y 1/2 mile is rugged terrain with two 100' high ledges. The southerly 1/2 mile is flat and much easier going. I checked the original record as referenced above: 1) checks, 2) & 3) did not measure to these, 4) 28.995 M, a distinct call, 5) 30.303M again, a well defined call, 6) Reestablished the corner at 40.691ch, (2685.60'), 7) 40.02M I believe this should have been 39.00 ch in original rather than 41.00: i.e. 1ch N rather than S of corner, 8) & 9) not distinct enough to use, 10) 77.58 M. I reestablished the corner at an indexed record distance north of C7 (2646.6'M) on a straight line between C7 and C5. I used an index of +13.1' per mile - the mean excess of 9 other miles remeasured in this township (s.dev. 5.1'). From this position, 4,5,7,10,11 above are in accord with the record, or nearly so.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C6) Set a 1"IDx36" iron pipe capped with a 4" dia. cast aluminum MNHR tablet, appropriately stamped. Blazed and scribed the following witnesses:

5" Cedar N08W 53.3' "1/4S NBT"
 10" Cedar N57E 48.2' "1/4S NBT"
 4" Aspen S32E 8.3' "1/4S NBT"
 2" Balsam S71W 17.4' "1/4S NBT"
 14" Cedar stump S66E 7.3' "1/4S"

Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 2-22-95

Surveyor's Michigan License No. 33986