

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located in:

Corner Code #

1. Public Land Survey

T 42N R 28W

K9

T R

T R

T R

2. Property Controlling
in Section

S 26 T 42N R 28W

7

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

Jun 17 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(K9) Corner common to Sections 23-24-25-26. Corner remonumented in 1961 by Billy D. Buckler, RLS: "This corner was placed at old Cedar (down) which has been blazed many years ago. Distance checks to stream 58 links north; good corner 1 mile west and good corner 1 mile south. Found old stake of unknown origin near Corner. Corner lies on a very old beaver dam. Corner monument 1" pipe with 4" brass cap. Witnesses: 8" Balm of Gilead SW 05 links, 7" Balm of Gilead NW 11 links".

(7-Sec. 26) North 1/16 corner between Sections 25-26. Corner established in 1962 by Billy D. Buckler, RLS: "This corner was placed midway between Section Corner to North and 1/4 corner to south. Corner monument 1" pipe with 4" aluminum cap. Witnesses to corner: 8" W. Spruce N70E 23 links, 7" W. Spruce S41E 18 links".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K9) Recovered the 1961 monument, as described, in good condition, but leaning slightly. I reset the monument to be in accord with the record bearings and distances from the 1961 witness trees. The NW tree is in good condition. The SW is dead and down. Marked three new accessories as described below. Corner reset and re-witnessed by B. Wheeler and D. Lampela, Baraga District Office, MDNR. No measurements to other corners were made at this time. This corner is being rerecorded in order to update the accessories.

(7-Sec. 26) Recovered the 1962 monument as described, in good condition, and at record bearing and distance from the rotting stump remains of the 1962 witnesses. Left the monument in place and marked four new accessories as described below. No measurements to other corner were made at this time. This corner is being rerecorded in order to update the accessories. Corner recovered and re-witnessed by D. Lampela and B. Wheeler, Baraga District Office, MDNR.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K9) Found 1" pipe with 4" brass MI Dept. of Conservation cap. The 1961 witness Balm of Gilead bears N15W 7.3' Blazed and scribed the following:
 8" B. Ash S79E 16.3' "S25 NBT"
 10" Balm of Gilead N27E 10.7' "S24 NBT"
 4" B. Ash S60W 22.9' "S26 NBT"
 Placed a squared cedar post adjacent.
 Bearings are magnetic.

(7) Found 1" pipe with 4" MDNR cap. Blazed and scribed the following:
 11" W. Spruce N56E 38.6' "1/16S NBT"
 3" W. Spruce S45E 56.3' "1/16S NBT"
 5" Double Spruce S43.5W 48.6' do
 10" W. Spruce N89W 19.1' "1/16S NBT"
 Placed a squared cedar post adjacent.
 Bearings are magnetic.



Signed by

Stephan J. SzyszkoskiSurveyor's Michigan License No. 33986

Date

9/2/97

For the Michigan Department of Natural Resources - Forest Management Division