

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Dickinson _____ Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 42N R 28W K10
T 42N R 28W J9
T R
T R

2. Property Controlling S T R
In Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Jun 17 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (K10) Quarter corner common to Sections 25-26. Corner reestablished in 1961 by Billy D. Buckler, RLS: This corner was re-established midway and on line between two section corners. Found no evidence of original corner. Area has been cleared for road building. Corner monument: 1" pipe with 4" brass cap. Witnesses to corner: 7" Cedar S42W 54 links, 6" Cedar S72E 79.5 links".
 (J9) Quarter corner common to Sections 23-26. Corner reestablished in 1962 by Billy D. Buckler, RLS: "This corner was placed midway and on line between section corners. No original evidence. Corner monument: 1" iron pipe with 4" brass cap. Witnesses to corner: 5" H. Maple N08W 13 links, 10" Elm S22W 35.5 links".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (K10) Found the 1961 monument as described, in good condition, in place, but disturbed. Reset the monument in accord with the 1961 cedar NBTs, both found in good condition. Marked two new witnesses as described below. No measurements were made to other corners at this time. This corner is being rerecorded in order to update the accessories. Corner recovered and rewitnessed by D. Lampela and B. Wheeler, Baraga District Office, MDNR.
 (J9) Found the 1962 monument as described, in good condition, and at record bearing and distance from the 1962 witnesses. The Hard Maple is in good condition, the Elm is dead. Left the monument in place and marked three new accessories as described below. No measurements were made to other corners at this time. This corner is being rerecorded in order to update the accessories. Corner recovered and rewitnessed by B. Wheeler and D. Lampela, Baraga District Office, MDNR.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (K10) Found 1" pipe with 4" MI Dept. of Conservation cap. Blazed and scribed the following new bearing trees:
 8" Tamarack NS2E 50.8' 1/4S NBT"
 8" Cedar N77W 52.6' 1/4S NBT"
 Placed a squared cedar post adjacent. Bearings are magnetic.
 (J9) Found 1" iron pipe with 4" MI Dept. of Conservation cap. The 1962 witness:
 8" Sugar N04W 8.35'
 Blazed and scribed the following:
 9" W. Spruce S66E 34.7' 1/4S NBT"
 5" W. Spruce South 47.45' 1/4S NBT"
 5" W. Spruce S53W 42.0' 1/4S NBT"
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 9/2/97
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources - Forest Management Division