

144

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Dickinson

(County)

Located In:

Corner Code #

1. Public Land Survey	T	42NR	28W	F2
	T	R		
	T	R		
	T	R		
2. Property Controlling in Section	S	26	T 42NR 28W	2
	S	T	R	
3. Miscellaneous	S	T	R	
Property in Sec.	S	T	R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

2 Jun 17 1997
F2 Jun 19 1997

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5				●	3	2	1				
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9										●			
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(F2) Center of Section 4. Corner established in 1989 by D.B. Babbitt, RLS: "Set at the intersection of the N-S and E-W 1/4 lines of Section 4. Set DNR monument (Buried in Road) 5" Maple N44E 36.9", 8" Maple S30E 30.95", 6" Maple S37W 37.1", 4" Ironwood N39W 38.3". (2-Sec. 26) East 1/16 corner between Sections 23-26. Corner established in 1962 by Billy D. Buckler, RLS: "This corner was placed midway and on line between section corner and 1/4 corner. Corner monument: 1" iron pipe with 4" brass cap. Witnesses to corner: 12" Balsam S63W 46 links, 10" Spruce N11W 51.5 links".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


(F2) Found the 1989 monument, as described, in good condition, and at record bearing and distance from the two remaining bearing trees: The maple and Ironwood NE and NW. The maples south of the road have been recently cut. This corner lies in the approximate center of an E-W road. Left the monument in place and marked two new accessories as described below. Corner recovered and re-witnessed by B. Wheeler and D. Lampela, Baraga District Office, MDNR. No measurements to other corners were made at this time. This corner is being rerecorded in order to update the accessories.

(2-Sec. 26) Found the 1962 monument, as described, in good condition, and at record bearing and distance from the 1962 witnesses. The balsam is now a rotten stump, and the spruce is in good condition. Left the monument in place and marked three new accessories as described below. No measurements to other corners were made at this time. This corner is being rerecorded in order to update the accessories. Corner recovered and re-witnessed by B. Wheeler and D. Lampela, Baraga District Office, MDNR.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F2) Found 1" pipe with 4" MDNR cap, buried. Blazed and scribed the following new bearing trees:
12" Maple S07W 39.5'
6" Maple S18E 30.1'
Bearings are magnetic.

(2) Found 1" pipe with 4" MI. Dept. of Conservation cap. The 1962 witness:
10" Spruce N11W 33.5'
Blazed and scribed the following:
10" Basswood S18E 13.8' "1/16S N8T"
5" Ironwood N79W 37.2' "1/16S N8T"
4" Ironwood N24.5E 53.5' "1/16S N8T"
Bearings are magnetic.



Signed by

Stephan J. Szyszkoski

Date

9/2/97

Surveyor's Michigan License No.

33986

For the Michigan Department of Natural Resources - Forest Management Division